



A Geosyntec Company

**Addendum #2
Request for Bids (RFB) 2023-05
Isle of Palms Marina – Public Dock and Intracoastal Dock Improvements
November 10, 2023**

This addendum is intended to provide further clarification to the Bid Documents for this project dated October 19, 2023.

Public Dock Clarification

The total pile length from the specified tip elevation of -58' NAVD88 to just below the decking on portions of the pier at deck elevation = +7.5' NAVD88 could be slightly greater than 65'. The use of 65' piles is acceptable understanding that the tip elevation shall be no shallower than -57' NAVD88.

End of Addendum #2